

DARTMOUTH



MASSACHUSETTS

DEPARTMENT OF PUBLIC WORKS

Acting Superintendent
David T. Hickox, P.E.

BOARD OF PUBLIC WORKS

Lee M. Azinheira
Manuel Branco
Richard R. Medeiros

May 16, 2006

CERTIFIED MAIL

Ms. Thelma Murphy, Storm Water Coordinator
United States Environmental Protection Agency
Municipal Assistance Unit (CMU)
One Congress Street – Suite 1100
Boston, MA 02114-2023

RE: Dartmouth, Massachusetts
NPDES Permit Number: MAR041102

Dear Ms. Murphy:

Please find enclosed one signed original NPDES PII Small MS4 General Permit Annual Report for the Town of Dartmouth signed by Michael J. Gagné, Executive Administrator for the Town of Dartmouth.

Should there be any questions, please feel free to contact me at (508) 999-0740.

Sincerely,
DEPARTMENT OF PUBLIC WORKS

David T. Hickox, P.E.
Acting Superintendent of Public Works

DTH:md

Municipality/Organization: Dartmouth, Massachusetts

EPA NPDES Permit Number: MAR041102

MaDEP Transmittal Number: W-

Annual Report Number

& Reporting Period: No. 3: March 05-March 06

NPDES PII Small MS4 General Permit Annual Report

Part I. General Information

Contact Person: David T. Hickox, P.E.

Title: Acting Superintendent

Telephone #: (508) 999-0740

Email: dhickox@town.dartmouth.ma.us

Certification:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature: 

Printed Name: Michael J. Gagne

Title: Executive Administrator

Date: May 15, 2006

Part II. Self-Assessment

The Town of Dartmouth Massachusetts has completed the required self-assessment and have determined that our municipality is in compliance with all permit conditions, except for the following provisions:

Section 1-2 Stencil Drainage Logo.

Revision: The Town has determined that the best visual impact and long term solution to the storm drain logo installation is the installation of permanent painted metal logos versus the painted stencil.

Section 3-1 Develop storm drain mapping based on aerial flight data, existing plans and field collected data.

Revision: The Town did not fund GIS mapping. The Town will coordinate the collection of field data with the New Bedford Vocational High School students utilizing GPS. Collected data will be downloaded and used in the development of a composite drainage map.

Part III. Summary of Minimum Control Measures

1. Public Education and Outreach

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
1-1 Revised	Partnerships <i>Award contract to create tributary signage.</i>	DPW, BOH Planning	Partnerships, Press releases, distribute .Maintain and replace as necessary tributary signs.	Partnered with Turn the Tide, including Lloyd Center, Coalition for Buzzards Bay, and Umass Dartmouth on a partnership to restore the health of Dartmouth coastal estuaries and rivers. Installed tributary signs..	Continue to evaluate and promote partnerships.
1-2 Revised	Educational Materials	DPW, BOH	Distribute Fact Sheets to municipal buildings, Paint winning "Storm Drain Stencil" in designated areas..	Town has purchased 1000 permanent storm water logos to be installed with college interns over the summer of 2006. Tributary signs have been installed.	Continue with the installation of storm water logos, fund storm drain programs at Town Meeting.
1-3 Revised	Reaching Diverse Audiences	DPW, BOH		The program was represented to the Board of Public Works and important program functions were detailed in the local newspaper along with color pictures of the new tributary signs .	Continue the installation of stormwater logos throughout Town. Include community groups in the installation effort. Board of Health to complete distribution of septic and grease trap maintenance information.
Revised					
Revised					

[illegible]

1a. Additions

2. Public Involvement and Participation

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
2-1 Revised	Storm Drain Stenciling	Planning, ConCom, DPW	Installation of logos.	Town has ordered and received 1000 metal stormwater logos including epoxy for installation on catch basin inlets..	Coordinate ongoing installation of storm drains logos with civic organizations, ie Boy Scouts, Buzzards Bay Coalition
2-2 Revised	Existing Program Assistance	DPW, ConCom	Update of the NPDES Phase II Program to Town Boards	Presentations were made by staff to the Board of Public Works. Met with local newspaper on story for the installation of the tribby=utary signs.	Maintain communication on storm water issues with various Boards.
Revised					
Revised					
Revised					
Revised					
Revised					
Revised					

2a. Additions

--	--	--	--	--	--

Page 1

Page 2

3. Illicit Discharge Detection and Elimination

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
3-1 Revised	Mapping	DPW, ConCom	Coordination of data collection with students from New Bedford Vocational High School	Met with representatives of the Buzzards Bay Coalition to coordinate data collection by New Bedford Vocational High School students utilizing hand held GPS units .	Establish priority areas for identification of illicit discharges. Solicit public input on potential problems.
3-2 Revised	Legal Prohibited – Enforcement	BOH, ConCom	Continued review and upgrading of existing stormwater related bylaws. Restrict feeding of geese.	Board of Health and Conservation Commission regulations have been reviewed to strengthen if required areas that prohibit illicit connections to storm drain systems. Identified potential sewage/drain overflow source and worked with party to identify and resolve problem..	Monitor regulations and revise as necessary. Review need to remove geese from Apponagansett Bay Watershed.
3-3 Revised	Detection Plan	BOH, DPW	Water quality testing and monitoring.	The Town continued to fund and partnership with the Loyd Center for Environmental Studies and the University of Massachusetts on the water quality testing and stream flow monitoring as part of the Turn the Tides Project. Prioritize areas for drainage review.	Continue Turn the Tides partnership and based on water quality testing results, the Town will move forward with the Source Location phase on the Detection Plan. The Town's I/I test equipment will be used to aid in the location of illicit connections.
3-4	Awareness & Education	BOH, Planning	Update the placement of Fact Sheets in Public Facilities, prepare and fund Household Hazardous Waste Day.	Fact sheets and Stormwater informational brochures have been obtained and displayed, Hazardous Waste Days have been advertised and held at the DPW Highway Yard.	Corrective action will be documented and local the newspaper will be informed as to the problem and solution.

4. Construction Site Stormwater Runoff Control

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
4-1	Stormwater Management	ConCom	Providing Stormwater Management Guidelines & Requirements	The Town has completed the upgrade of the aquifer protection bylaw and the bylaw has been approved by Town Meeting . Conservation Commission has inventoried structural storm water technologies within the Town . Continued the review of standards for Stormwater related to the construction of residential and commercial developments.	Continue the review of regulations as necessary and incorporate bylaw revisions as the pertain to stormwater and new Aquifer Protection guidelines.
Revised					
4-2	Stormwater Regulations	Planning Board	Review of Subdivision Regulations relative to stormwater control during construction.	Enforcement of subdivision regulations that prevent the release of residential lots for sale until all stormwater facilities have been constructed and are fully operational.	Review, update and implement stormwater regulations relative to construction activities.
Revised					
4-3	Education Materials	DPW	Provide Stormwater Information to all contractors that have been awarded construction contracts with the Department of Public Works.	All contractors performing site work or utility work on significant size projects are provided with a Memorandum and wall guide to Planning & Implementing Erosion & Sediment Control Practices.	Continue to provide information to contractors involved in site development related projects.
Revised					
Revised					
Revised					

Revised						

4a. Additions

5. Post-Construction Stormwater Management in New Development and Redevelopment

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
5-1	Stormwater Management	ConCom	Enforcement of Town of Dartmouth's and Mass DEP's Stormwater Guidelines.	Ongoing review and monitoring of the current stormwater bylaws and regulations. The Town has a designated drainage consultant who is responsible for the review of all stormwater designs. The Town's Environmental Affairs Coordinator monitors all construction related activities.	Continue the current post construction monitoring of sites.
Revised					
5-2	Drainage Consultant	ConCom	Consistent Technical Review of Stormwater design and policy.	Consultant provided technical input to the Aquifer Protection Bylaw Committee during the Bylaw upgrade in preparation for Town Meeting. Consultant continued the review of all Notice of Intent drainage calculations.	Continue Consultant reviews.
Revised					
5-3	Subdivision Rules & Regulations	Planning	Enforcement of regulations pertaining to stormwater facilities being fully operational prior to release of lots.	Developers are aware that they must construct all drainage facilities, and provide fully operational system prior to the release of any lot for sale.	Monitor and update regulations as needed.

6. Pollution Prevention and Good Housekeeping in Municipal Operations

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) – Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities – Permit Year 4
6-1	Employee Training	DPW	Provide employee training in conjunction with 40 CFR 112 program.	DPW has completed a review of the SPCC Plan. Review stormwater related policies to be presented in the training program.	Continue annual training of employees in stormwater related procedures.
Revised					
6-2	O&M Program	DPW	Implementation of O&M program designed to reduce and or eliminate the discharge of pollutants from various DPW facilities.	DPW Highway Division has all road salt/sand is stored within the salt shed. Staff monitors all exterior stored equipment for fluid leakage. Stormwater detention ponds at the Highway Division garage have been serviced and the remaining Highway Division Yard is swept clean of salt residues, the existing oil/gas separator has been fully serviced after the winter season in preparation for the new season	Town will continue to solicit funding for a new “salt only” covered facility. Grants and other funding sources will be explored.
Revised					
6-3	Roadway Maintenance	DPW	Sweep all streets. Clean all catch basins annually.	The Town swept all primary roadways and a majority of secondary roadways. The Town has cleaned all catch basins in Town under private contract.	The sweeping of all primary streets prior to the cleaning of catch basins to allow for improved operation of the deep sump catch basin design.
Revised					
Revised					
Revised					
Revised					

6a. Additions

7. BMPs for Meeting Total Maximum Daily Load (TMDL) Waste Load Allocations (WLA) << if applicable >>

BMP ID #	BMP Description	Responsible Dept./Person Name	Measurable Goal(s)	Progress on Goal(s) -- Permit Year 3 (Reliance on non-municipal partners indicated, if any)	Planned Activities -- Permit Year 4
7-1	BMP's for TMDL Reduction	DPW	Implement BMP's for existing stormwater facilities..	Town has purchased a Vacuum Truck for servicing stormwater facilities. Town has completed design, permitting and installation of Vortechnic Unit funded by a DEP grant. Town is currently planning the installation of a new vortechnic unit BMP for Paskemansett Bay .	Continue administrative record for monitoring reductions in TMDL's resulting from the installation new BMP's on existing watersheds.
Revised					
Revised					
Revised					
Revised					
Revised					
Revised					
Revised					

7a. Additions

--	--	--	--	--

--	--	--	--	--	--

7b. WLA Assessment

Part IV. Summary of Information Collected and Analyzed

- The Coalition for Buzzards Bay has provided an informational section in their newsletter on Dartmouth's Phase II Storm Water Management Program. The summary provides a general overview of the Phase II Program.
- Extensive research and debate has taken place over the last year and a new Dartmouth Aquifer Protection Bylaw has been approved by Town Meeting. Professional Staff and residents working together have evaluated the pro's and con's of impervious cover, recharge, new BMP's for stormwater, O&M of new BMP's, monitoring and certification on operation of various new technologies.
- The Town's ongoing support and contribution of \$336,000 to partner with the Lloyd Center, The Coalition for Buzzards Bay, and the University of Massachusetts on the Turn the Tide Project is a commitment by the Town to protect it's most natural asset by restoring the health and vitality of Dartmouth's waters.
- The program has completed the installation of all tributary signs and has replacement signs available for installation in the event of damage of theft.
- The program has publicized the issue of illegal dumping and has worked with local newspaper to print related stories.
- The Conservation Commission has categorized all structural storm water units in Town.
- A significant stormwater/sanitary sewer related problem was identified and corrected.
- The Town funded and purchased 1000 storm water logos.

Part V. Program Outputs & Accomplishments (OPTIONAL)

Programmatic

Stormwater management position created/staffed	(y/n)	
Annual program budget/expenditures	(\$)	

Education, Involvement, and Training

Estimated number of residents reached by education program(s)	(# or %)	
Stormwater management committee established	(y/n)	
Stream teams established or supported	(# or y/n)	
Shoreline clean-up participation or quantity of shoreline miles cleaned	(y/n or mi.)	
Household Hazardous Waste Collection Days		
▪ days sponsored	(#)	
▪ community participation	(%)	
▪ material collected	(tons or gal)	
School curricula implemented	(y/n)	

Legal/Regulatory

In Place	Under	Drafted	Adopted
Prior to	Review		
Phase II			

Regulatory Mechanism Status (indicate with "X")				
▪ Illicit Discharge Detection & Elimination				
▪ Erosion & Sediment Control				
▪ Post-Development Stormwater Management				
Accompanying Regulation Status (indicate with "X")				
▪ Illicit Discharge Detection & Elimination				
▪ Erosion & Sediment Control				
▪ Post-Development Stormwater Management				

Mapping and Illicit Discharges

Outfall mapping complete		(%)	
Estimated or actual number of outfalls		(#)	
System-Wide mapping complete		(%)	
Mapping method(s)			
▪ Paper/Mylar		(%)	
▪ CADD		(%)	
▪ GIS		(%)	
Outfalls inspected/screened		(# or %)	
Illicit discharges identified		(#)	
Illicit connections removed		(#)	
		(est. gpd)	
% of population on sewer		(%)	
% of population on septic systems		(%)	

Construction

Number of construction starts (> 1-acre)		(#)	
Estimated percentage of construction starts adequately regulated for erosion and sediment control		(%)	

Site inspections completed	(# or %)	
Tickets/Stop work orders issued	(# or %)	
Fines collected	(# and \$)	
Complaints/concerns received from public	(#)	

Post-Development Stormwater Management

Estimated percentage of development/redevelopment projects adequately regulated for post-construction stormwater control	(%)	
Site inspections completed	(# or %)	
Estimated volume of stormwater recharged	(gpy)	

Operations and Maintenance

Average frequency of catch basin cleaning (non-commercial/non-arterial streets)	(times/yr)	
Average frequency of catch basin cleaning (commercial/arterial or other critical streets)	(times/yr)	
Total number of structures cleaned	(#)	
Storm drain cleaned	(LF or mi.)	
Qty. of screenings/debris removed from storm sewer infrastructure	(lbs. or tons)	
Disposal or use of sweepings (landfill, POTW, compost, recycle for sand, beneficial use, etc.)		
Cost of screenings disposal	(\$)	

Average frequency of street sweeping (non-commercial/non-arterial streets)	(times/yr)	
Average frequency of street sweeping (commercial/arterial or other critical streets)	(times/yr)	
Qty. of sand/debris collected by sweeping	(lbs. or tons)	
Disposal of sweepings (landfill, POTW, compost, beneficial use, etc.)	(location)	
Cost of sweepings disposal	(\$)	

Vacuum street sweepers purchased/leased	(#)
Vacuum street sweepers specified in contracts	(y/n)

Reduction in application on public land of: ("N/A" = never used; "100%" = elimination)	
▪ Fertilizers	(lbs. or %)
▪ Herbicides	(lbs. or %)
▪ Pesticides	(lbs. or %)

Anti-/De-Icing products and ratios	% NaCl % CaCl ₂ % MgCl ₂ % CMA % Kac % KCl % Sand
Pre-wetting techniques utilized	(y/n)
Manual control spreaders used	(y/n)
Automatic or Zero-velocity spreaders used	(y/n)
Estimated net reduction in typical year salt application	(lbs. or %)
Salt pile(s) covered in storage shed(s)	(y/n)
Storage shed(s) in design or under construction	(y/n)